
## DISTRICT 6



**Gus Pego** 



## Significant Projects

- 95 Express
- Palmetto Expressway
- Port of Miami Tunnel
- NW 25 Street
- Miami Intermodal Center





Florida Department of Transportation in conjunction with Miami-Dade and Broward County

Transportation Partners

#### What is The Problem?

- South Florida 10<sup>th</sup> worst traffic congestion in nation!
- Population to continue growing
- I-95 volumes are nearly 300,000 vehicles per day (360,000 by 2030)
- Congestion wastes 150 million hours annually costing \$2.5 billion





#### **Existing Conditions**



- South Florida Population Projection: 45% growth (1.7 million people) between 2000 and 2030
- HOV lanes and General Use lanes break down during rush hour:
  - General Use lanes average 13 to 16 mph
  - HOV lanes average 20 to 31 mph
- 18% of total person throughput on HOV lane results from Express Bus Service
- High Demand for Express Bus Service at Golden Glades – but bus service travel time is not reliable on HOV lane

#### **The Solution**


- FDOT applying for special federal funding from the Urban Partnership Agreement program for Interstate 95 Managed Lanes Project '95 Express'
- Required components 4 T's
  - Tolling (Congestion Management)
  - Transit (Bus Rapid Transit)
  - Technology (SunPass)
  - Telecommuting (Flex-time Programs)




#### **4 T Solutions**

- Existing General Use Lanes maintained
- Addition of 2 new lanes for length of 21 mile corridor via restriping
- 95 Express New lanes & existing HOV lanes converted to Managed Lanes
- Variable Congestion Pricing will help maintain free flowing operations (approx. min. speed of 50 MPH) in Managed Lanes
- Only Limited Construction Required (Phase 1A and 1B), construction limited to shoulders and SR 112/I-195 Interchange modifications
- Expedited Implementation


#### 95 Express Configuration





#### **Managed Lanes Network**

- 21 Miles from I-395 in Miami to I-595 in Fort Lauderdale
- Meant for longer trips
- Five entry/exit points planned
- Future network: I-595, I-75, HEFT, US
   1, SR 836, SR 826



#### 95 Express Benefits Transit, Motorists, and Businesses



- New Bus Rapid Transit routes
- Provides for reliable transit schedules
- Four Managed Lanes in operation along 21 mile corridor between Miami and Ft. Lauderdale
- 95 Express toll revenues will support facility costs and help provide funding support for Bus Rapid Transit
- Provides a new choice for consistent and dependable travel conditions
- Improved park-n-ride facilities

#### Bus Rapid Service (BRT)



#### **Expanded Transit with 95 Express**

- Eliminate County-line transfer
- Miami-Dade 95 Express bus service extended along I-95 north to Ft. Lauderdale
- Broward US 441 & University Drive bus service extended into I-95 south to Miami
- Further Expansion additional future routes and route extensions



#### Technology & Telecommuting

- South Florida peak hour transponder usage is 70% on existing toll expressways
- Buses, Registered HOV, and Vanpools will be issued non-revenue decals
- South Florida Commuter Services (SFCS) Outreach to be expanded
- SFCS will prepare customized transportation plans for Employers and Employees dependant on the I-95 Corridor.
- UPA Outreach: Mobilize resources to reach out to 75 businesses and 20,000 employees in 6 months prior to startup.



South Florida Commuter Services www.1800234ride.com







## PALMETTO EXPRESSWAY (SR 826) EXPANSION PROJECTS


#### **Project Overview**

#### **PROJECT HISTORY**

- Corridor first built in the late 1950s
- Expanded in the mid-1970s
- Steady increase in traffic during the 1980s
- Beginning in the early 1990s
   Palmetto Expansion Program divided into 12 sections



#### SR 826 (PALMETTO EXPRESSWAY) IMPROVEMENT PROGRAM



SECTION 3	
FM No.	2496481
COMPLETED YEAR	2008
ROW COST:	\$ 3,815,000 (2002)
PHASE 52: \$	45,103,000 (2004)
PROJECT LENGTH	I.O (MILE)

SECTION 5	
FM No.	2495811
COMPLETED YEAR	-
ROW COST:	\$ 178,000,000 (2008)
PHASE 52: \$	552,550,000 (2008)
PROJECT LENGTH	1.6 (MILES)

FM No. 2496501	
COMPLETED YEAR	2006
ROW COST:	\$ 1,424,000 (2002
PHASE 52: \$	38,916,000 (2003)
PROJECT LENGTH	1.2 (MILES)

SECTION 9	
FM No.	2496521
COMPLETED YEAR	2007
ROW COST:	\$ 3,141,000 (2002)
PHASE 52: \$	28,765,000 (2002)
PROJECT LENGTH	0.9 (MILE)



FM No.	2494271
COMPLETED YEAR	2004
ROW COST:	\$ 0
PHASE 52: \$	26,254,000 (1993)
PROJECT LENGTH	3.0 (MILES)

SECTION 2	
FM No.	2490351
COMPLETED YEAR	2011
ROW COST:	\$ 7,276,000 (2005)
PHASE 52: \$	176,806,000 (2008)
PROJECT LENGTH	2.4 (MILES)

SECTION 4	
FM No.	2496491
COMPLETED YEAR	2008
ROW COST:	\$ 0
PHASE 52: \$	38,425,000
PROJECT LENGTH	0.9 (MILE)

SECTION 6	
FM No.	2491121
COMPLETED YEAR	-
ROW COST:	\$ 1,842,000 (1992)
PHASE 52: \$	16,108,000 (2000)
PROJECT LENGTH	IJ (MILES)
	1

NW 25th STREET

NW 36th STREET

SECTION 8	
FM No.	24965//
COMPLETED YEAR	2001
ROW COST:	\$ 237,000 (1993)
PHASE 52: \$	14,609,000 (1999)
PROJECT LENGTH	1.3 (MILES)

FM No.	2496531
COMPLETED YEAR	2007
ROW COST:	\$ 2,447,000 (2002)
PHASE 52: \$	41,903,000 (2002)
PROJECT LENGTH	0.9 (WILE)

SECTION 11	
FM No.	2491131
COMPLETED YEAR	2002
ROW COST:	\$ 17,354,000 (1999)
PHASE 52: \$	40,317,000 (1999)
PROJECT LENGTH	1.2 (MILES)

1-75

**BEGIN PROJECT** US 1 SR 986 (SUNSET DR.) SW 72nd STREET

SR 94 (KENDALL DR.) SW 88th STREET

SR 976 (BIRD ROAD) SW 40th STREET (MILLER DR.) SW 56th STREET

SR 90 (TAMIAMI TRAIL) SW 8th STREET (CORAL WAY) SW 24th STREET

SR 968 (FLAGLER STREET) SR 836 (DOLPHIN EXWY)

OKEECHOBEE ROAD **NW 58th STREET** HIALEAH EXPRESSWAY NW 74th STREET

**NW 122nd STREET** SR 932 (49th STREET) NW 103rd ST

**NW 154th STREET** NW 138th STREET GRATIGNY PRKWY

END PROJECT

**SR-826 TO I-75 NB RAMP** FM No. 4102611 COMPLETED YEAR 2004 ROW COST: \$ 0 6,696,000 (2002) PHASE 52: \$ PROJECT LENGTH 1.2 (MILES)

**SECTION 2 Project Overview** 

**Begin Project** 

#### PROPOSED IMPROVEMENTS

- Reconstruction of the Palmetto Expressway including the addition of travel lanes in each direction
- Reconstructing the Palmetto Expressway
   Interchanges at Bird Road, Miller Drive and SR 874
- New storm water drainage system throughout the project area
- Replacing the existing Pedestrian Bridge just north of Bird Road
- Numerous enhancements to SW 40th St. and SW 56th St., including new traffic signals, street signs and street lighting
- Project includes the addition of median barrier walls as well as new barrier walls along the outside lanes
- Installing landscape
- Installing two eight-inch watermains



#### **SECTION 2 Project Overview**

#### **CONSTRUCTION SCHEDULE**

Anticipated construction schedule: Three years


#### **RIGHT-OF-WAY**

- All Right-of-Way has been acquired
- FDOT will enforce limited access to the frontage roads and strive to minimize construction impacts
- Staging areas to be determined and approved by the FDOT
- Tennis/dust screens will be installed temporarily during construction

#### **COST AND FUNDING**

- The cost of construction is an estimated \$177 million
- MDX is contributing \$60 Million due to the improvements of the SR 874 facility
- Design-Build Finance Project

#### **Typical Section North of Bird Road**



#### **Section 2 Project Benefits**

#### TRAFFIC IMPROVEMENTS

 Less congestion and improved traffic flow along one of Miami-Dade County's most vital corridors

#### SAFETY ENHANCEMENTS

- Smoother, safer access to and from the expressway at Bird Road, Miller Drive and SR 874 interchanges
- Enhanced safety along Bird Road and Miller Drive

#### PEDESTRIAN IMPROVEMENTS

Enhanced pedestrian features

#### **WATER QUALITY**


 Drainage system is being replaced with a more efficient system to collect and treat a greater amount of rain water

#### LANDSCAPING AESTHETICS

- Install low maintenance landscape within project limits
- Future project to provide additional landscaping along mainline to follow after construction



# SR 826 (Palmetto Expressway) Improvement Program Section 5 SR 826 / SR 836 Interchange



## **Section 5 Project Limits:**

#### The Section 5 construction limits are as follows:

Approximately 9,200 feet on SR 826 Approximately 15,100 feet on SR 836



## **Section 5 Project Description:**

- Reconstruction of SR 826 (Palmetto Expressway)
- Reconstruction of SR 836 (Dolphin Expressway)
- Construction of direct connectors to provide traffic movements between the two expressways in all directions.





### SR 826 / SR 836 Master Plan



## **Section 5 Project Benefits:**

- Construction of direct expressway-to-expressway connectors in all directions, including the non-existing North to West movement.
- Flip-flop of the Milam Dairy Road interchange that will improve the operational characteristics of the SR 826 / SR 836 Interchange.

Three additional lanes (one thru lane and two managed lanes) will be

provided for the SR 836 Eastbound.

Two additional lanes (managed lanes) will be provided for the SR 836 Westbound.



## **Section 5 Project Benefits:**

- Connector from SR 836 Westbound managed lanes to SR 826 Southbound and from SR 826 Northbound to SR 836 Eastbound managed lanes will be provided.
- ❖ All left entrances/exits from SR 836 mainlines will be eliminated.
- Due to the reconstruction of the SR 826/West Flagler interchange afternoon peak-hour backups along SR 836 Westbound will be reduced drastically.
- ❖ Due to the construction of Ramp E-N and Bridge 11, morning peak-hour backups along SR 836 Eastbound in the area West of the SR 826 expressway will be reduced drastically.
- Standard outside shoulder width will be provided throughout all mainlines and ramps.

## **Section 5 Project Benefits:**

❖ Traffic weaving along Eastbound and Westbound of SR 836 in the area between NW 72<sup>nd</sup> Avenue and SR 826 will be eliminated.

Entrances and exits to local roads will be done by means of the Eastbound and Westbound CD's.

- Window for the future East-West transit corridor is being provided.
- Access for future transit station at the southeast quadrant of the Interchange is being provided.
- SR 826 has been raised to provide a window for the future connection of NW 7<sup>th</sup> Street.
- SR 836 has been raised to provide a window for the future connection of NW 82<sup>nd</sup> Avenue.

## Port Access Project: The Port of Miami Tunnel









## Port Access: Importance of Port

- POM is top international cruise terminal, 10<sup>th</sup> international cargo port based on containerized shipments, and top seaport in Florida based on dollar volume
  - \$20.7 billion in imports/exports
  - **81,800** jobs
  - \$5 billion in wages
  - -\$12 billion in economic output

## Port Access: Truck traffic will increase

- 26,000 vehicles
   (Nearly 7,000 trucks & buses) travel to/from
   POM through
   downtown streets
- By 2030, estimated truck traffic
   will nearly double






# Port Access: Existing truck routes through Downtown Miami

- Trucks
   currently travel
   through NE 1
   and 2<sup>nd</sup>
   Avenue
- Must go
   through 6 to 7
   signals
   inbound and
   outbound



#### Port Access: Benefits

- Provide direct connection from Port to I-395 via Watson Island
- Keep Port
   competitive –
   (County's second leading economic
   generator)
- Relieve downtown congestion



## Funding the POMT

- Capital Cost 50/50 State/Local Partnership
- Risk Sharing/Private Sector:
  - \$100 million during construction
  - \$350 million upon POMT completion
  - Remaining in annual "availability payment"
    - Covers both remaining capital and annual operations and maintenance costs
    - Proposal at \$33 million in 2007 dollars (indexed)
  - \$120 million contingency reserve (\$10 concessionaire \$90 FDOT/Local \$20 concessionaire)

## Port Access: Building the Tunnel

- Involves specially-constructed Tunnel Boring Machine approx. 42 ft. high
- TBM consists of cutter head and trailing support gear
- Excavation will take just over one year—6 months in each direction





# Port Access: FDOT Procurement Schedule

•	December 5, 2005	Industry Forum
•	February 17, 2006	Releases Request for Qualifications
•	April 12, 2006	Receives Statement of Qualifications from potential bidders
•	April 28, 2006	Announces short-list of bidders
•	November 1, 2006	Publishes Request for Proposals
•	March 5, 2007	Receives proposals from 3 short- listed bidders
•	May 2, 2007	Best Value Proposal named – MAT
•	February 15, 2008	Notice of Intent to Award
•	December 2008	MAT (Miami Access Tunnel) Contract

#### Port Access:

### Design/Construction Schedule

#### 5-Year Design/Construction Period

2009

Final design / Permitting

Utility relocation

2010

Excavation for tunnels

POM roadways & bridges

<u>2011</u>

U-Walls / Approaches

2012

Tunnel finishes

Support facilities

2013

Complete tunnel & roadways

Tunnel systems, testing and startup



# Port Access: Funding the POMT


- FDOT contributing 50% of capital cost (\$432.5 million) from Strategic Intermodal System (SIS) funds
- Local partners have matched capital costs
- FDOT funding tunnel Operations & Maintenance from statewide maintenance funds (about \$200 million over 30 years)







#### NW 25<sup>th</sup> Street Viaduct From SR 826 to NW 68<sup>th</sup> Avenue



**Contract Amount** \$118 Million

**Status** 48% Complete

Construction Began 09/10/2007

**Anticipated Completion** 07/10/2011

Contractor
De Moya Group, Inc.

## Miami Intermodal Center (MIC) and Rental Car Facility (RCF) and MIC / MIA Station



**Combined Contract Amount** \$ 350 Million

MIC RCF Construction Schedule 07/09/2007 to 09/20/2009 56% Complete

MIC/MIA Station
Construction Schedule
05/21/2008 to 09/17/2010
13% Complete



#### FTBA Award for Partnering

Reconstruction and widening of SR 826/Palmetto Expressway and Interchanges at Coral Way (SW 24th St) and SR 90 (SW 8th St)



FDOT Design Project Manager Erki Suarez, PE / Ali Toghiani, PE

FDOT Designer – Coral Way
Nathaniel Pulido

Design Consultant – SW 8<sup>th</sup> St Donald Ambroise Corradino Group, Inc.

FDOT Construction Project Manager
Dari Vorce

Consultant Engineering Inspection
Tim Sears, PE
A2 Group

Contractor

APAC SE – Major Projects Group


Contract Amount \$82 Million

Final Acceptance 01/28/2008

#### FTBA Award for Interchange

#### MIC Package 2

Provide connectivity between the Miami Intermodal Center and the major arterials servicing the Miami International Airport



FDOT Design Project Manager Kouroche Mohandes, PE

> Design Consultant Ubaldo F. Lena, PE URS Corporation

FDOT Construction Project Manager Isa M. Nunez, PE

Construction Engineering Inspection
Gus Quesada, PE
Bermello, Ajamil & Partner

**Contractor Kiewit Southern Corporation** 

**Contract Amount** \$ 72 Million

Final Acceptance 05/13/2008

#### FTBA Award for Design Build

#### SR 5/US1 Reconstruction from MM 113 to MM 116



FDOT Design Project Manager
Luis Tellechea

FDOT Construction Project Manager
Dari Vorce

Construction Engineering Inspection
Pom Chakkaphak
Parsons Brinkerhoff Construction
Services

**Contractor Community Asphalt Corporation** 

**Contract Amount** \$ 40 Million

Final Acceptance 06/30/2008

#### FTBA Award for Minor Bridge

#### SR 9A/I-95 Widening

Widening three consecutive interstate bridges and addition of one mainline rigid concrete pavement lane



FDOT Design Project Manager
Jason Chang, PE

Design Consultant Robert T. Carballo, PE C3TS

FDOT Construction Project Manager Ivan Hay, PE

Construction Engineering Inspection Francis R. Chin, PE AIM Engineering & Surveying, Inc.


**Contractor Kiewit Southern Corporation** 

**Contract Amount** \$ 12 Million

Final Acceptance 06/02/2008

#### FTBA Award for Utility Coordination

## Biscayne Boulevard Reconstruction Reconstruction from NE 78th Street to NE 87th Street



FDOT Design Project Manager Mohammed Mansuri, PE

FDOT Designer Erenia Nagid

FDOT Construction Project Manager Ivan Hay, PE

Construction Engineering Inspection
Steven McCue, PE
New Millennium Engineering, Inc.

**Contractor**Community Asphalt Corporation

**Contract Amount** \$ 7.5 Million

Final Acceptance 07/01/2008

## QUESTIONS?